

## **PRECAST, PRESTRESSED CONCRETE BEAMS**

Effective: October 5, 2015

Revise the second paragraph of Article 504.07(b) to read as follows.

“Precast, prestressed concrete I-beams, Bulb T-beams, or IL-beams will be measured by the foot (meter). In determining the total length of beams to be paid for, the specified overall length of the individual beams will be used.”

Revise the first paragraph of Article 504.08 to read as follows.

**“Basis of Payment.** This work will be paid for at the contract unit price per square foot (square meter) for PRECAST CONCRETE BRIDGE SLAB and PRECAST, PRESTRESSED CONCRETE DECK BEAMS, of the depth specified, or per foot (meter) for FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, of the depth specified, or FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS, of the depth specified, or FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BEAMS, of the type specified.”