CROSSHOLE SONIC LOGGING TESTING OF DRILLED SHAFTS

Effective: April 20, 2016 Revised: August 9, 2019

<u>Description.</u> This work shall consist of furnishing and installing materials and equipment necessary to install access ducts in all drilled shafts of structures identified on the plans, and to perform Crosshole Sonic Logging (CSL) testing of selected drilled shafts on these structures. This work shall be according to Illinois Modified ASTM D6760. This work also includes analysis of the CSL data, preparation of reports summarizing the CSL data, and investigating anomalies identified in the CSL data. This work shall also include grouting of all access ducts after testing and approval by the Engineer.

Materials. Materials shall be according to the following.

Qualifications. A consulting firm experienced in CSL testing shall conduct this work. The CSL consulting firm shall be a company independent from the Contractor with a minimum of 3 years of experience in performing CSL testing of drilled shafts. The individual employee of the CSL consulting firm performing analysis of the CSL data and preparing the report shall be an Illinois Licensed Professional Engineer and have experience on a minimum of 5 projects performing CSL testing of drilled shafts.

The name, contact information, and qualifications of the CSL consulting firm, including the names and experience of the individual employees performing and analyzing the test results and preparing the report, shall be submitted to the Engineer at least 30 days prior to drilled shaft construction.

<u>Construction.</u> Access ducts shall be placed in all drilled shafts for the structures indicated on the plans, attached to the reinforcement cage and situated symmetrically around the diameter of the shaft according to the Illinois Modified ASTM D6760. The Engineer will determine which drilled shafts shall have CSL testing performed after the concrete has been placed in the drilled shafts, and may direct additional tests, if necessary, due to problems encountered or observed during drilled shaft construction.

After permission is given by the Engineer, the access ducts shall be grouted. The grout shall be placed with a pump, starting at the bottom of each access duct.

Superimposed loads, either dead or live, shall not be applied to a drilled shaft until CSL testing is completed, CSL reports have been submitted, any necessary repairs have been completed, access ducts have been grouted, and permission has been granted by the Engineer.

<u>Reports.</u> Reports shall be according to Illinois Modified ASTM D6760. Each anomalous zone detected by the CSL testing shall be identified and discussed in the report. An anomalous zone shall be defined as areas where velocity reduction exceeds 20 percent of the average velocity of properly placed and cured shaft concrete at the time of testing.

<u>Anomalies.</u> If anomalies are identified, they shall be investigated by coring or other methods approved by the Engineer.

<u>Correction of Drilled Shaft Defects.</u> When testing determines that a defect is present, the Engineer will direct the Contractor to submit remedial measures for approval. No compensation will be made for remedial work, or losses, or damage, due to remedial work of drilled shafts found defective or not in accordance with the drilled shaft specifications or plans. Modifications to the drilled shaft design, or any load transfer mechanisms required by the remedial action, must be designed, detailed, and sealed by an Illinois Licensed Structural Engineer, and submitted for approval.

<u>Method of Measurement.</u> Installation and grouting of access ducts will be measured for payment per shaft by the linear foot of drilled shaft(s) with access ducts.

CSL testing, analysis, and reporting will be measured for payment by each drilled shaft foundation tested.

Investigation of anomalies will not be measured for payment.

<u>Basis of Payment.</u> Installation and grouting of access ducts will be paid for at the contract unit price per foot for CROSSHOLE SONIC LOGGING ACCESS DUCTS. CSL testing, analysis, and reporting will be paid for at the contract unit price per each for CROSSHOLE SONIC LOGGING TESTING.

ILLINOIS MODIFIED ASTM D6760

Effective Date: August 9, 2019

Standard Test Method for

Integrity Testing of Concrete Deep Foundations by Ultrasonic Crosshole Testing

Reference ASTM D6760-14

ASTM SECTION	Illinois Modifi	Illinois Modification		
3.1.1	Revise this s			
	access ducts, n – preformed steel tubes or drilled boreholes, placed			
	in the concrete to allow probe entry in pairs to measure pulse			
	transmission in the concrete between the probes.			
6.1	Revise the se	Revise the second sentence of this section as follows:		
	The tubes shall be mild steel.			
	Delete the th	Delete the third, fourth, and fifth sentences of this section.		
7.1.1	Revise this s	Revise this section as follows:		
	The access ducts shall be installed during construction of the drilled			
	shaft.			
	For drilled shafts foundations, access ducts shall be provided			
	according to	according to the following table.		
		Reinforcing Cage	Number of access ducts	
		Diameter (feet)		
		≤ 4.0	3	
		4.1 to 5.0	4	
		5.1 to 7.0	6	
		> 7.0	8	
		Access ducts shall be spread equally around the perimeter and		
	spaced at an equal distance from the axis.			
	Delete Fig. 4.			
7.1.2	Revise the second sentence of this section as follows:			
	The exterior tube surface shall be free from contamination (for			
		example, oil, dirt, loose rust, mill scale, etc.) to ensure a good bond		
	1	tube surface and the su		
7.1.3	Delete the th	Delete the third sentence of this section.		

ILLINOIS MODIFIED ASTM D6760

Effective Date: August 9, 2019

Standard Test Method for

Integrity Testing of Concrete Deep Foundations by Ultrasonic Crosshole Testing

Reference ASTM D6760-14

7.2	Revise the first sentence of this section as follows: The access tubes shall be installed such that their bottom is within 4 inches of the bottom of the concrete deep foundation element so that the bottom condition can be tested.
	Revise the sixth sentence of this section as follows: Access tubes shall be filled with water prior to concrete placement to assure good bonding of the concrete to the tube after the concrete cools. The access tubes shall be kept full of water until the tubes are grouted.
7.3	Revise the first sentence of this section as follows: In cases where drilled shafts to be tested have access ducts that do not permit passage of the probes, do not retain water, are not plumb, are debonded from the concrete, or cannot be used for testing for other reasons, drilled boreholes shall be used to provide probe access.
7.4.2	Revise the second sentence of this section as follows: The tests shall be performed no later than 21 days after concrete casting.
7.6	Delete this section.
7.8.1	Revise the first sentence of this section as follows: If the ultrasonic profile indicates an anomaly, then the suspect anomaly zone shall be further investigated by special test procedures such as fan shaped tests, tests with the probes raised at a fixed offset distance, or other tomographical techniques (1, 2).
7.8.2	Delete Note 5 of this section.