







CELL / MODEL NAME	DESCRIPTION	DATE
IL27-1830	27" Prestressed I-Bm. - 18" & 30" Flanges	2/17/2017
IL27-1830D	27" Prestressed I-Bm. - 18" & 30" Flanges - Detail Sheet	2/17/2017
IL36-2438	36" Prestressed I-Bm. - 24" & 38" Flanges	2/17/2017
IL36-2438D	36" Prestressed I-Bm. - 24" & 38" Flanges - Detail Sheet	2/17/2017
IL36-3838	36" Prestressed I-Bm. - 38" Flanges	2/17/2017
IL36-3838D	36" Prestressed I-Bm. - 38" Flanges - Detail Sheet	2/17/2017
IL45-2438	45" Prestressed I-Bm. - 24" & 38" Flanges	2/17/2017
IL45-2438D	45" Prestressed I-Bm. - 24" & 38" Flanges - Detail Sheet	2/17/2017
IL45-3838	45" Prestressed I-Bm. - 38" Flanges	2/17/2017
IL45-3838D	45" Prestressed I-Bm. - 38" Flanges - Detail Sheet	2/17/2017
IL54-2438	54" Prestressed I-Bm. - 24" & 38" Flanges	2/17/2017
IL54-2438D	54" Prestressed I-Bm. - 24" & 38" Flanges - Detail Sheet	2/17/2017
IL54-3838	54" Prestressed I-Bm. - 38" Flanges	2/17/2017
IL54-3838D	54" Prestressed I-Bm. - 38" Flanges - Detail Sheet	2/17/2017
IL63-2438	63" Prestressed I-Bm. - 24" & 38" Flanges	2/17/2017
IL63-2438D	63" Prestressed I-Bm. - 24" & 38" Flanges - Detail Sheet	2/17/2017
IL63-3838	63" Prestressed I-Bm. - 38" Flanges	2/17/2017
IL63-3838D	63" Prestressed I-Bm. - 38" Flanges - Detail Sheet	2/17/2017
IL72-2438	72" Prestressed I-Bm. - 24" & 38" Flanges	2/17/2017
IL72-2438D	72" Prestressed I-Bm. - 24" & 38" Flanges - Detail Sheet	2/17/2017
IL72-3838	72" Prestressed I-Bm. - 38" Flanges	2/17/2017
IL72-3838D	72" Prestressed I-Bm. - 38" Flanges - Detail Sheet	2/17/2017
PBT-4-63	63 inch PPC bulb T beam	2/17/2017
PBT-4-63D	63 inch PPC bulb T beam details	2/17/2017
PBT-4-72	72 inch PPC bulb T beam	2/17/2017
PBT-4-72D	72 inch PPC bulb T beam details	2/17/2017
PI-4-36	36 inch PPC I beam	2/17/2017
PI-4-36D	36 inch PPC I beam details	2/17/2017
PI-4-42	42 inch PPC I beam	2/17/2017
PI-4-42D	42 inch PPC I beam details	2/17/2017
PI-4-48	48 inch PPC I beam	2/17/2017
PI-4-48D	48 inch PPC I beam details	2/17/2017
PI-4-54	54 inch PPC I beam	2/17/2017

CELL / MODEL NAME	DESCRIPTION	DATE
PI-4-54D	54 inch PPC I beam details	2/17/2017




IL27-1830


2-17-2017

Note:
See sheet of for additional
details and Bill of Material.


FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL27N BEAM STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -					CONTRACT NO.		
	PLOT DATE =	CHECKED -	REVISED -					ILLINOIS FED. AID PROJECT		



PLAN - TOP PLATE




ELEVATION - BOTTOM
PLATE ASSEMBLY




SECTION E-E

** 3 Spaces at 2 1/2 inch = 7 1/2 inch

*** 2 Spaces at 3 inch = 6 inch




BAR G1(E)




M1 WWR DETAIL

When multiple sheets of M1 WWR are required along the beam length, #5(E) bars (5'-0" long) shall be used to splice the longitudinal D31 wires together (Min. Lap 2'-2").



M4 THRU M6 WWR DETAIL

(See Table of Dimensions)



M2 AND M3 WWR DETAIL

(See Table of Dimensions)

NOTES

Inserts for 3/4" Ø threaded dowel rods, when specified, are to be two strut, ferrule type for interior beams and single ferrule, flared loop type for exterior beams.

Prestressing steel shall be uncoated high strength, low relaxation 7-wire strand, Grade 270. The nominal diameter for beam strands shall be 0.6" and the nominal cross-sectional area shall be 0.217 sq. in. The nominal diameter for lifting loops shall be 1/2" and the nominal cross sectional area shall be 0.153 sq. in.

The beams shall have a final concrete compressive strength, f'c, of 8500 psi and a release concrete compressive strength, f'ci, of 7000 psi.

A minimum 2 1/2" Ø lifting pin shall be used to engage the lifting loops during handling.

Bend the extended strands inward on the fascia beams to maintain 1 1/2" clearance inside the pier diaphragm.

The top and bottom plates shall be AASHTO M270 Grade 50.

The top plates and bottom plate assemblies shall be galvanized according to AASHTO M111. The threaded rods, nuts and washers shall be galvanized according to AASHTO M232.

Threaded rods shall be ASTM F 1554 Grade 55.

Beams shall not be released from the fabricator until they have attained 45 days of age or older.

Welded Wire Reinforcement (WWR) shall conform to ASTM A884 with a Class A, Type 1 epoxy coating.


TABLE OF DIMENSIONS

SPAN

WWR	A	B
M2	15	3"
M3	-	1'-6"
M4	6	3"
M5	-	6"
M6	-	1'-0"

SPAN

WWR	A	B
M2	15	3"
M3	-	1'-6"
M4	6	3"
M5	-	6"
M6	-	1'-0"



LIFTING LOOP DETAIL







BILL OF MATERIAL

Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete Beams, IL27N	Ft.	

IL27-1830D

2-17-2017

FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL27N BEAM DETAILS STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -					CONTRACT NO.		
	PLOT DATE =	CHECKED -	REVISED -					ILLINOIS FED. AID PROJECT		




Note:
See sheet of for additional details and Bill of Material.


IL36-2438

2-17-2017


FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL36N BEAM STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -							
	PLOT DATE =	CHECKED -	REVISED -							
							CONTRACT NO.			
						ILLINOIS FED. AID PROJECT				



PLAN - TOP PLATE




ELEVATION - BOTTOM PLATE ASSEMBLY




SECTION E-E

** 3 Spaces at 2 1/2" = 7 1/2"

*** 2 Spaces at 3" = 6"




BAR G1(E)




M1 WWR DETAIL

When multiple sheets of M1 WWR are required along the beam length, #5(E) bars (5'-0" long) shall be used to splice the longitudinal D31 wires together (Min. Lap 2'-2").



M5 THRU M8 WWR DETAIL

(See Table of Dimensions)



M2 THRU M4 WWR DETAIL

(See Table of Dimensions)

NOTES

Inserts for 3/4" Ø threaded dowel rods, when specified, are to be two strut, ferrule type for interior beams and single ferrule, flared loop type for exterior beams. Prestressing steel shall be uncoated high strength, low relaxation 7-wire strand, Grade 270. The nominal diameter for beam strands shall be 0.6" and the nominal cross-sectional area shall be 0.217 sq. in. The nominal diameter for lifting loops shall be 1/2" and the nominal cross sectional area shall be 0.153 sq. in.

The beams shall have a final concrete compressive strength, f'c, of 8500 psi and a release concrete compressive strength, f'ci, of 7000 psi.

A minimum 2 1/2" Ø lifting pin shall be used to engage the lifting loops during handling.

Bend the extended strands inward on the fascia beams to maintain 1 1/2" clearance inside the pier diaphragm.

The top and bottom plates shall be AASHTO M270 Grade 50.

The top plates and bottom plate assemblies shall be galvanized according to AASHTO M111.

The threaded rods, nuts and washers shall be galvanized according to AASHTO M232.

Threaded rods shall be ASTM F 1554 Grade 55.

Beams shall not be released from the fabricator until they have attained 45 days of age or older.

Welded Wire Reinforcement (WWR) shall conform to ASTM A884 with a Class A, Type 1 epoxy coating.


TABLE OF DIMENSIONS

SPAN

WWR	A	B
M2	9	3"
M3	6	6"
M4	-	1'-6"
M5	9	3"
M6	-	6"
M7	-	1'-0"
M8	-	2'-0"

SPAN

WWR	A	B
M2	9	3"
M3	6	6"
M4	-	1'-6"
M5	9	3"
M6	-	6"
M7	-	1'-0"
M8	-	2'-0"



LIFTING LOOP DETAIL







BILL OF MATERIAL

Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete Beams, IL36N	Ft.	

IL36-2438D

2-17-2017

FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL36N BEAM DETAILS STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
		CHECKED -	REVISED -									
	PLOT SCALE =	DRAWN -	REVISED -									
	PLOT DATE =	CHECKED -	REVISED -									
						CONTRACT NO.						
						ILLINOIS FED. AID PROJECT						




Note:
See sheet of for additional
details and Bill of Material.


IL36-3838

2-17-2017


FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL36 BEAM STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -					CONTRACT NO.		
	PLOT DATE =	CHECKED -	REVISED -					ILLINOIS FED. AID PROJECT		



PLAN - TOP PLATE




ELEVATION - BOTTOM PLATE ASSEMBLY




SECTION E-E

** 3 Spaces at 2 1/2" = 7 1/2"

*** 2 Spaces at 3" = 6"




BAR G1(E)




M1 WWR DETAIL

When multiple sheets of M1 WWR are required along the beam length, #5(E) bars (5'-0" long) shall be used to splice the longitudinal D31 wires together (Min. Lap 2'-2").



M5 THRU M8 WWR DETAIL

(See Table of Dimensions)




M2 THRU M4 WWR DETAIL

(See Table of Dimensions)

TABLE OF DIMENSIONS


SPAN		
WWR	A	B
M2	9	3"
M3	6	6"
M4	-	1'-6"
M5	9	3"
M6	-	6"
M7	-	1'-0"
M8	-	2'-0"

SPAN		
WWR	A	B
M2	9	3"
M3	6	6"
M4	-	1'-6"
M5	9	3"
M6	-	6"
M7	-	1'-0"
M8	-	2'-0"



SECTION THRU TOP FLANGE

(Showing limits of bond breaker)



LIFTING LOOP DETAIL





BILL OF MATERIAL


Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete Beams, IL36	Ft.	

IL36-3838D


2-17-2017

FILE NAME =	USER NAME =	DESIGNED -	REVISD -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL36 BEAM DETAILS STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISD -							
PLOT SCALE =		DRAWN -	REVISD -							
PLOT DATE =		CHECKED -	REVISD -							
						CONTRACT NO.				
						ILLINOIS FED. AID PROJECT				






PLAN - TOP PLATE




ELEVATION - BOTTOM
PLATE ASSEMBLY




SECTION E-E

** 3 Spaces at 2 1/2" = 7 1/2"

*** 2 Spaces at 3" = 6"




BAR G1(E)




M1 WWR DETAIL

When multiple sheets of M1 WWR are required along the beam length, #5(E) bars (5'-0" long) shall be used to splice the longitudinal D31 wires together (Min. Lap 2'-2").



M5 THRU M8 WWR DETAIL

(See Table of Dimensions)



M2 THRU M4 WWR DETAIL

(See Table of Dimensions)

NOTES

Inserts for 3/4" Ø threaded dowel rods, when specified, are to be two strut, ferrule type for interior beams and single ferrule, flared loop type for exterior beams. Prestressing steel shall be uncoated high strength, low relaxation 7-wire strand, Grade 270. The nominal diameter for beam strands shall be 0.6" and the nominal cross-sectional area shall be 0.217 sq. in. The nominal diameter for lifting loops shall be 1/2" and the nominal cross sectional area shall be 0.153 sq. in.

The beams shall have a final concrete compressive strength, f'c, of 8500 psi and a release concrete compressive strength, f'ci, of 7000 psi.

A minimum 2 1/2" Ø lifting pin shall be used to engage the lifting loops during handling.

Bend the extended strands inward on the fascia beams to maintain 1 1/2" clearance inside the pier diaphragm.

The top and bottom plates shall be AASHTO M270 Grade 50.

The top plates and bottom plate assemblies shall be galvanized according to AASHTO M111.

The threaded rods, nuts and washers shall be galvanized according to AASHTO M232.

Threaded rods shall be ASTM F 1554 Grade 55.

Beams shall not be released from the fabricator until they have attained 45 days of age or older.

Welded Wire Reinforcement (WWR) shall conform to ASTM A884 with a Class A, Type 1 epoxy coating.


TABLE OF DIMENSIONS

SPAN

WWR	A	B
M2	9	3"
M3	9	6"
M4	-	1'-6"
M5	12	3"
M6	-	6"
M7	-	1'-0"
M8	-	2'-0"

SPAN

WWR	A	B
M2	9	3"
M3	9	6"
M4	-	1'-6"
M5	12	3"
M6	-	6"
M7	-	1'-0"
M8	-	2'-0"



LIFTING LOOP DETAIL







BILL OF MATERIAL

Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete Beams, IL45N	Ft.	

IL45-2438D

2-17-2017

FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL45N BEAM DETAILS STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -					CONTRACT NO.		
	PLOT DATE =	CHECKED -	REVISED -					ILLINOIS FED. AID PROJECT		



Note:
See sheet of for additional
details and Bill of Material.

IL45-3838


2-17-2017

FILE NAME =	USER NAME =	DESIGNED -	REVISED -
		CHECKED -	REVISED -
	PLOT SCALE =	DRAWN -	REVISED -
	PLOT DATE =	CHECKED -	REVISED -


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL45 BEAM
STRUCTURE NO.


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
ILLINOIS FED. AID PROJECT				



PLAN - TOP PLATE




ELEVATION - BOTTOM PLATE ASSEMBLY




SECTION E-E

** 3 Spaces at 2 1/2" = 7 1/2"

*** 2 Spaces at 3" = 6"




BAR G1(E)




M1 WWR DETAIL

When multiple sheets of M1 WWR are required along the beam length, #5(E) bars (5'-0" long) shall be used to splice the longitudinal D31 wires together (Min. Lap 2'-2").



M5 THRU M8 WWR DETAIL

(See Table of Dimensions)




M2 THRU M4 WWR DETAIL

(See Table of Dimensions)

TABLE OF DIMENSIONS


SPAN		
WWR	A	B
M2	9	3"
M3	9	6"
M4	-	1'-6"
M5	12	3"
M6	-	6"
M7	-	1'-0"
M8	-	2'-0"

SPAN		
WWR	A	B
M2	9	3"
M3	9	6"
M4	-	1'-6"
M5	12	3"
M6	-	6"
M7	-	1'-0"
M8	-	2'-0"



SECTION THRU TOP FLANGE

(Showing limits of bond breaker)



LIFTING LOOP DETAIL


BILL OF MATERIAL

Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete Beams, IL45	Ft.	


IL45-3838D

2-17-2017


FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL45 BEAM DETAILS STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	CHECKED -	REVISIED -	REVISIED -							
	PLOT SCALE =	DRAWN -	REVISIED -			CONTRACT NO.				
	PLOT DATE =	CHECKED -	REVISIED -			ILLINOIS FED. AID PROJECT				



PLAN - TOP PLATE




ELEVATION - BOTTOM PLATE ASSEMBLY




SECTION E-E

** 3 Spaces at 2 1/2" = 7 1/2"

*** 2 Spaces at 3" = 6"




BAR G1(E)




M1 WWR DETAIL

When multiple sheets of M1 WWR are required along the beam length, #5(E) bars (5'-0" long) shall be used to splice the longitudinal D31 wires together (Min. Lap 2'-2").



M5 THRU M8 WWR DETAIL

(See Table of Dimensions)



M2 THRU M4 WWR DETAIL

(See Table of Dimensions)

TABLE OF DIMENSIONS

SPAN

WWR	A	B
M2	9	3"
M3	12	6"
M4	-	1'-6"
M5	15	3"
M6	-	6"
M7	-	1'-0"
M8	-	2'-0"

SPAN

WWR	A	B
M2	9	3"
M3	12	6"
M4	-	1'-6"
M5	15	3"
M6	-	6"
M7	-	1'-0"
M8	-	2'-0"

NOTES

Inserts for 3/4" Ø threaded dowel rods, when specified, are to be two strut, ferrule type for interior beams and single ferrule, flared loop type for exterior beams. Prestressing steel shall be uncoated high strength, low relaxation 7-wire strand, Grade 270. The nominal diameter for beam strands shall be 0.6" and the nominal cross-sectional area shall be 0.217 sq. in. The nominal diameter for lifting loops shall be 1/2" and the nominal cross sectional area shall be 0.153 sq. in.

The beams shall have a final concrete compressive strength, f'c, of 8500 psi and a release concrete compressive strength, f'ci, of 7000 psi.

A minimum 2 1/2" Ø lifting pin shall be used to engage the lifting loops during handling.

Bend the extended strands inward on the fascia beams to maintain 1 1/2" clearance inside the pier diaphragm.

The top and bottom plates shall be AASHTO M270 Grade 50.


The top plates and bottom plate assemblies shall be galvanized according to AASHTO M111.

The threaded rods, nuts and washers shall be galvanized according to AASHTO M232.

Threaded rods shall be ASTM F 1554 Grade 55.

Beams shall not be released from the fabricator until they have attained 45 days of age or older.

Welded Wire Reinforcement (WWR) shall conform to ASTM A884 with a Class A, Type 1 epoxy coating.



LIFTING LOOP DETAIL




BILL OF MATERIAL

Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete Beams, IL54N	Ft.	




IL54-2438D

2-17-2017

FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL54N BEAM DETAILS STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -					CONTRACT NO.		
	PLOT DATE =	CHECKED -	REVISED -					ILLINOIS FED. AID PROJECT		



SECTION B-B
* Only tighten sufficiently to compress lock washers




○ Fully bonded strand
▲ Partially debonded strand

Note:
See sheet of for additional details and Bill of Material.


IL54-3838

2-17-2017


FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL54 BEAM STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
		CHECKED -	REVISED -									
PLOT SCALE =		DRAWN -	REVISED -									
PLOT DATE =		CHECKED -	REVISED -									
						CONTRACT NO.						
						ILLINOIS FED. AID PROJECT						



PLAN - TOP PLATE




ELEVATION - BOTTOM PLATE ASSEMBLY




SECTION E-E

** 3 Spaces at 2 1/2" = 7 1/2"

*** 2 Spaces at 3" = 6"




BAR G1(E)




M1 WWR DETAIL

When multiple sheets of M1 WWR are required along the beam length, #5(E) bars (5'-0" long) shall be used to splice the longitudinal D31 wires together (Min. Lap 2'-2").



M5 THRU M8 WWR DETAIL

(See Table of Dimensions)



M2 THRU M4 WWR DETAIL

(See Table of Dimensions)

TABLE OF DIMENSIONS

SPAN		
WWR	A	B
M2	9	3"
M3	12	6"
M4	-	1'-6"
M5	15	3"
M6	-	6"
M7	-	1'-0"
M8	-	2'-0"

SPAN		
WWR	A	B
M2	9	3"
M3	12	6"
M4	-	1'-6"
M5	15	3"
M6	-	6"
M7	-	1'-0"
M8	-	2'-0"

NOTES

Inserts for 3/4" Ø threaded dowel rods, when specified, are to be two strut, ferrule type for interior beams and single ferrule, flared loop type for exterior beams. Prestressing steel shall be uncoated high strength, low relaxation 7-wire strand, Grade 270. The nominal diameter for beam strands shall be 0.6" and the nominal cross-sectional area shall be 0.217 sq. in. The nominal diameter for lifting loops shall be 1/2" and the nominal cross sectional area shall be 0.153 sq. in.

The beams shall have a final concrete compressive strength, f'c, of 8500 psi and a release concrete compressive strength, f'ci, of 7000 psi.

A minimum 2 1/2" Ø lifting pin shall be used to engage the lifting loops during handling.

Bend the extended strands inward on the fascia beams to maintain 1 1/2" clearance inside the pier diaphragm.

The top and bottom plates shall be AASHTO M270 Grade 50.


The top plates and bottom plate assemblies shall be galvanized according to AASHTO M111.

The threaded rods, nuts and washers shall be galvanized according to AASHTO M232.


Threaded rods shall be ASTM F 1554 Grade 55.

Beams shall not be released from the fabricator until they have attained 45 days of age or older.

Welded Wire Reinforcement (WWR) shall conform to ASTM A884 with a Class A, Type 1 epoxy coating.



SECTION THRU TOP FLANGE



LIFTING LOOP DETAIL







BILL OF MATERIAL

Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete Beams, IL54	Ft.	

IL54-3838D

2-17-2017

FILE NAME =	USER NAME =	DESIGNED -	REVISD -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL54 BEAM DETAILS STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISD -							
PLOT SCALE =		DRAWN -	REVISD -					CONTRACT NO.		
PLOT DATE =		CHECKED -	REVISD -					ILLINOIS FED. AID PROJECT		




Note:
See sheet of for additional details and Bill of Material.


IL63-2438

2-17-2017


FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL63N BEAM STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
		CHECKED -	REVISED -									
	PLOT SCALE =	DRAWN -	REVISED -									
	PLOT DATE =	CHECKED -	REVISED -									
						CONTRACT NO.						
						ILLINOIS FED. AID PROJECT						



PLAN - TOP PLATE




ELEVATION - BOTTOM PLATE ASSEMBLY




SECTION E-E

** 3 Spaces at 2 1/2" = 7 1/2"

*** 2 Spaces at 3" = 6"




BAR G1(E)




M1 WWR DETAIL

When multiple sheets of M1 WWR are required along the beam length, #5(E) bars (5'-0" long) shall be used to splice the longitudinal D31 wires together (Min. Lap 2'-2").



M5 THRU M8 WWR DETAIL

(See Table of Dimensions)



M2 THRU M4 WWR DETAIL

(See Table of Dimensions)

TABLE OF DIMENSIONS

SPAN

WWR	A	B
M2	9	3"
M3	15	6"
M4	-	1'-6"
M5	18	3"
M6	-	6"
M7	-	1'-0"
M8	-	2'-0"

SPAN

WWR	A	B
M2	9	3"
M3	15	6"
M4	-	1'-6"
M5	18	3"
M6	-	6"
M7	-	1'-0"
M8	-	2'-0"

NOTES

Inserts for 3/4" Ø threaded dowel rods, when specified, are to be two strut, ferrule type for interior beams and single ferrule, flared loop type for exterior beams. Prestressing steel shall be uncoated high strength, low relaxation 7-wire strand, Grade 270. The nominal diameter for beam strands shall be 0.6" and the nominal cross-sectional area shall be 0.217 sq. in. The nominal diameter for lifting loops shall be 1/2" and the nominal cross sectional area shall be 0.153 sq. in.

The beams shall have a final concrete compressive strength, f'c, of 8500 psi and a release concrete compressive strength, f'ci, of 7000 psi.

A minimum 2 1/2" Ø lifting pin shall be used to engage the lifting loops during handling.

Bend the extended strands inward on the fascia beams to maintain 1 1/2" clearance inside the pier diaphragm.

The top and bottom plates shall be AASHTO M270 Grade 50.


The top plates and bottom plate assemblies shall be galvanized according to AASHTO M111.

The threaded rods, nuts and washers shall be galvanized according to AASHTO M232.

Threaded rods shall be ASTM F 1554 Grade 55.

Beams shall not be released from the fabricator until they have attained 45 days of age or older.

Welded Wire Reinforcement (WWR) shall conform to ASTM A884 with a Class A, Type 1 epoxy coating.



LIFTING LOOP DETAIL


BILL OF MATERIAL

Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete Beams, IL63N	Ft.	

IL63-2438D

2-17-2017


FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL63N BEAM DETAILS STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -					CONTRACT NO.		
	PLOT DATE =	CHECKED -	REVISED -					ILLINOIS FED. AID PROJECT		




*** 2 Spaces at 3" = 6"



When multiple sheets of M1 WWR are required along the beam length, #5(E) bars (5'-0" long) shall be used to splice the longitudinal D31 wires together (Min. Lap 2'-2").



(See Table of Dimensions)



(See Table of Dimensions)

TABLE OF DIMENSIONS

<u>SPAN</u>		
WWR	A	B
M2	9	3"
M3	15	6"
M4	-	1'-6"
M5	18	3"
M6	-	6"
M7	-	1'-0"
M8	-	2'-0"

<u>SPAN</u>		
WWR	A	B
M2	9	3"
M3	15	6"
M4	-	1'-6"
M5	18	3"
M6	-	6"
M7	-	1'-0"
M8	-	2'-0"




BILL OF MATERIAL


Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete Beams, IL63	Ft.	

2-17-2017


FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL63 BEAM DETAILS STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		CHECKED -	REVISED -								
	PLOT SCALE =	DRAWN -	REVISED -			CONTRACT NO.					
	PLOT DATE =	CHECKED -	REVISED -			ILLINOIS FED. AID PROJECT					



PLAN - TOP PLATE




ELEVATION - BOTTOM PLATE ASSEMBLY




SECTION E-E

** 3 Spaces at 2 1/2" = 7 1/2"

*** 2 Spaces at 3" = 6"




BAR G1(E)




M1 WWR DETAIL

When multiple sheets of M1 WWR are required along the beam length, #5(E) bars (5'-0" long) shall be used to splice the longitudinal D31 wires together (Min. Lap 2'-2").



M5 THRU M8 WWR DETAIL

(See Table of Dimensions)



M2 THRU M4 WWR DETAIL

(See Table of Dimensions)

NOTES

Inserts for 3/4" Ø threaded dowel rods, when specified, are to be two strut, ferrule type for interior beams and single ferrule, flared loop type for exterior beams. Prestressing steel shall be uncoated high strength, low relaxation 7-wire strand, Grade 270. The nominal diameter for beam strands shall be 0.6" and the nominal cross-sectional area shall be 0.217 sq. in. The nominal diameter for lifting loops shall be 1/2" and the nominal cross sectional area shall be 0.153 sq. in.

The beams shall have a final concrete compressive strength, f'c, of 8500 psi and a release concrete compressive strength, f'ci, of 7000 psi.

A minimum 2 1/2" Ø lifting pin shall be used to engage the lifting loops during handling.

Bend the extended strands inward on the fascia beams to maintain 1 1/2" clearance inside the pier diaphragm.

The top and bottom plates shall be AASHTO M270 Grade 50.

The top plates and bottom plate assemblies shall be galvanized according to AASHTO M111.

The threaded rods, nuts and washers shall be galvanized according to AASHTO M232.

Threaded rods shall be ASTM F 1554 Grade 55.

Beams shall not be released from the fabricator until they have attained 45 days of age or older.

Welded Wire Reinforcement (WWR) shall conform to ASTM A884 with a Class A, Type 1 epoxy coating.


TABLE OF DIMENSIONS

SPAN

WWR	A	B
M2	9	3"
M3	18	6"
M4	-	1'-6"
M5	21	3"
M6	-	6"
M7	-	1'-0"
M8	-	2'-0"

SPAN

WWR	A	B
M2	9	3"
M3	18	6"
M4	-	1'-6"
M5	21	3"
M6	-	6"
M7	-	1'-0"
M8	-	2'-0"



LIFTING LOOP DETAIL


BILL OF MATERIAL

Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete Beams, IL72N	Ft.	


IL72-2438D

2-17-2017


FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL72N BEAM DETAILS STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -							
	PLOT DATE =	CHECKED -	REVISED -							
							CONTRACT NO.			
						ILLINOIS FED. AID PROJECT				



PLAN - TOP PLATE




ELEVATION - BOTTOM PLATE ASSEMBLY




SECTION E-E

** 3 Spaces at 2 1/2" = 7 1/2"

*** 2 Spaces at 3" = 6"




BAR G1(E)




M1 WWR DETAIL

When multiple sheets of M1 WWR are required along the beam length, #5(E) bars (5'-0" long) shall be used to splice the longitudinal D31 wires together (Min. Lap 2'-2").



M5 THRU M8 WWR DETAIL

(See Table of Dimensions)




M2 THRU M4 WWR DETAIL

(See Table of Dimensions)


TABLE OF DIMENSIONS

SPAN		
WWR	A	B
M2	9	3"
M3	18	6"
M4	-	1'-6"
M5	21	3"
M6	-	6"
M7	-	1'-0"
M8	-	2'-0"

SPAN		
WWR	A	B
M2	9	3"
M3	18	6"
M4	-	1'-6"
M5	21	3"
M6	-	6"
M7	-	1'-0"
M8	-	2'-0"



SECTION THRU TOP FLANGE



LIFTING LOOP DETAIL


BILL OF MATERIAL

Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete Beams, IL72	Ft.	


IL72-3838D

2-17-2017

FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL72 BEAM DETAILS STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -					CONTRACT NO.		
	PLOT DATE =	CHECKED -	REVISED -					ILLINOIS FED. AID PROJECT		



ELEVATION OF BEAM
(Showing reinforcement & dimensions)



SECTION A-A


** Only tighten sufficiently to compress lock washers

SECTION B-B


BAR LIST
ONE BEAM ONLY
(For information only)

Bar	No.	Size	Length	Shape
G1(E)		#4	12'-1"	⏏ L
G2(E)		#4	10'-2"	⏏
G3(E)		#6		—
G4(E)		#3	4'-11"	⏏
G5(E)		#5	3'-4"	—
G6(E)		#8	6'-6"	⏏


Notes:
See sheet of for additional details and Bill of Material.



SECTION C-C
(-1/2" Ø 270 ksi strands)



ELEVATION OF BEAM
(Showing prestressing steel)



SECTION THRU TOP FLANGE
(Showing limits of bond breaker)

PBT-4-63

2-17-2017

FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	63" PPC BULB T-BEAM STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -					CONTRACT NO.		
	PLOT DATE =	CHECKED -	REVISED -					ILLINOIS FED. AID PROJECT		

NOTES

Inserts for 3/4" Ø threaded dowel rods, when specified, are to be two strut, ferrule type for interior beams and single ferrule, flared loop type for exterior beams. Prestressing steel shall be uncoated high strength, low relaxation 7-wire strand, Grade 270. The nominal diameter shall be 1/2" and the nominal cross-sectional area shall be 0.153 sq. in.

The beams shall have a final concrete compressive strength, f'c, of psi and a release concrete compressive strength, f'ci, of psi.

A minimum 2 1/2" Ø lifting pin shall be used to engage the lifting loops during handling.

Tilt G6(E) bars when necessary to maintain 1 1/2" clearance.


The top and bottom plates shall be AASHTO M270 Grade 50.

The top and bottom plates shall be galvanized according to AASHTO M111. The threaded rods, nuts and washers shall be galvanized according to AASHTO M232.


Threaded rods shall be ASTM F 1554 Grade 55.

The G6(E) bar assembly shall develop, in tension, at least 125 percent of the yield strength of a grade 60 reinforcement bar times the nominal cross-sectional area of a #8 bar. The assembly shall allow completion of the splice without turning of the hook bar. The hook bar shall be threaded such that the entire coupler can be threaded onto the hook bar.


Beams shall not be released from the fabricator until they have attained 45 days of age or older.




ELEVATION OF BEAM AT PIER




PLAN OF BEAM AT PIER




LIFTING LOOP DETAIL




BAR G1(E)




BAR G2(E)



BAR G4(E)




TOP PLATE



BOTTOM PLATE

See bearing details for pintle hole locations when required.



G6(E) BAR ASSEMBLY


BILL OF MATERIAL

Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete Bulb T-Beams, 63"	Ft.	


PBT-4-63D

2-17-2017

FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	63" PPC BULB T-BEAM DETAILS STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -			CONTRACT NO.				
	PLOT DATE =	CHECKED -	REVISED -			ILLINOIS FED. AID PROJECT				




ELEVATION OF BEAM
(Showing reinforcement & dimensions)




SECTION A-A

** Only tighten sufficiently to compress lock washers


SECTION B-B



ELEVATION OF BEAM
(Showing prestressing steel)



SECTION THRU TOP FLANGE
(Showing limits of bond breaker)



SECTION C-C
(- 1/2" Ø 270 ksi strands)

BAR LIST
ONE BEAM ONLY
(For information only)


Bar	No.	Size	Length	Shape
G1(E)		#4	13'-7"	⏏
G2(E)		#4	11'-8"	⏏
G3(E)		#6		⏏
G4(E)		#3	4'-11"	⏏
G5(E)		#5	3'-4"	⏏
G6(E)		#8	6'-6"	⏏

Notes:
See sheet of for additional details
and Bill of Material.


PBT-4-72

2-17-2017


FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	72" PPC BULB T-BEAM STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -					CONTRACT NO.		
	PLOT DATE =	CHECKED -	REVISED -					ILLINOIS FED. AID PROJECT		




ELEVATION OF BEAM AT PIER




PLAN OF BEAM AT PIER




LIFTING LOOP DETAIL




BAR G1(E)




BAR G2(E)



BAR G4(E)




TOP PLATE



BOTTOM PLATE

See bearing details for pintle hole locations when required.



G6(E) BAR ASSEMBLY





BILL OF MATERIAL

Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete Bulb T-Beams, 72"	Ft.	

PBT-4-72D

2-17-2017

FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	72" PPC BULB T-BEAM DETAILS STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -					CONTRACT NO.		
	PLOT DATE =	CHECKED -	REVISED -					ILLINOIS FED. AID PROJECT		



BAR LIST
ONE BEAM ONLY
(For information only)


Bar	No.	Size	Length	Shape
G1(E)		#4	7'-7"	⏏
G2(E)		#4	5'-8"	⏏
G3(E)		#5		—
G4(E)		#3	4'-1"	⏏
G6(E)		#8	6'-6"	⏏

Notes:
See sheet of for additional details and Bill of Material.


PI-4-36

2-17-2017


FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	36" PPC I-BEAM STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -					CONTRACT NO.		
	PLOT DATE =	CHECKED -	REVISED -					ILLINOIS FED. AID PROJECT		




ELEVATION OF BEAM AT PIER




PLAN OF BEAM AT PIER




LIFTING LOOP DETAIL




BAR G1(E)




BAR G2(E)



BAR G4(E)




TOP PLATE



BOTTOM PLATE

See bearing details for pintle hole locations when required.



G6(E) BAR ASSEMBLY


BILL OF MATERIAL

Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete I-Beams, 36"	Ft.	


PI-4-36D

2-17-2017

FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	36" PPC I-BEAM DETAILS STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -					CONTRACT NO.		
	PLOT DATE =	CHECKED -	REVISED -					ILLINOIS FED. AID PROJECT		



ELEVATION OF BEAM
(Showing reinforcement & dimensions)




SECTION A-A
**Only tighten sufficiently to compress lock washers

SECTION B-B

BAR LIST
ONE BEAM ONLY
(For information only)

Bar	No.	Size	Length	Shape
G1(E)		#4	8'-7"	⏏
G2(E)		#4	6'-8"	⏏
G3(E)		#6		⏏
G4(E)		#3	4'-11"	⏏
G5(E)		#3	2'-6"	⏏
G6(E)		#8	6'-6"	⏏

Notes:
See sheet of for additional details
and Bill of Material.




SECTION C-C
(-1/2" Ø 270 ksi strands)


PI-4-42

2-17-2017


FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	42" PPC I-BEAM STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -					CONTRACT NO.		
	PLOT DATE =	CHECKED -	REVISED -					ILLINOIS FED. AID PROJECT		




ELEVATION OF BEAM AT PIER




PLAN OF BEAM AT PIER




TOP PLATE




BOTTOM PLATE
(Showing threaded rods)




LIFTING LOOP DETAIL




BOTTOM PLATE
(Showing studs)




BAR G1(E)




BAR G2(E)



BAR G4(E)



G6(E) BAR ASSEMBLY



BAR G5(E)

NOTES

Inserts for 3/4" Ø threaded dowel rods, when specified, are to be two strut, ferrule type for interior beams and single ferrule, flared loop type for exterior beams. Prestressing steel shall be uncoated high strength, low relaxation 7-wire strand, Grade 270. The nominal diameter shall be 1/2" and the nominal cross-sectional area shall be 0.153 sq. in. The beams shall have a final concrete compressive strength, f'c, of -- psi and a release concrete compressive strength, f'ci, of -- psi. A minimum 2 1/2" Ø lifting pin shall be used to engage the lifting loops during handling. Tilt G6(E) bars when necessary to maintain 1 1/2" clearance. The top and bottom plates shall be AASHTO M270 Grade 50. The top and bottom plates shall be galvanized according to AASHTO M111. The threaded rods, nuts and washers shall be galvanized according to AASHTO M232. Threaded rods shall be ASTM F 1554 Grade 55. The G6(E) bar assembly shall develop, in tension, at least 125 percent of the yield strength of a grade 60 reinforcement bar times the nominal cross-sectional area of a #8 bar. The assembly shall allow completion of the splice without turning of the hook bar. The hook bar shall be threaded such that the entire coupler can be threaded onto the hook bar. Beams shall not be released from the fabricator until they have attained 45 days of age or older.


BILL OF MATERIAL

Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete 1-Beams, 42"	Ft.	


PI-4-42D

2-17-2017


FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	42" PPC I-BEAM DETAILS STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -					CONTRACT NO.		
	PLOT DATE =	CHECKED -	REVISED -					ILLINOIS FED. AID PROJECT		



ELEVATION OF BEAM
(Showing reinforcement & dimensions)



ELEVATION OF BEAM
(Showing prestressing steel)




SECTION A-A
** Only tighten sufficiently to compress lock washers

SECTION B-B

BAR LIST
ONE BEAM ONLY
(For information only)

Bar	No.	Size	Length	Shape
G1(E)		#4	9'-8"	⌚
G2(E)		#4	7'-11"	⌚
G3(E)		#7		⌚
G4(E)		#3	5'-3"	⌚
G5(E)		#3	2'-9"	⌚
G6(E)		#8	6'-6"	⌚

Notes:
See sheet of for additional details
and Bill of Material.




SECTION C-C
(-1/2" Ø 270 ksi strands)


PI-4-48

2-17-2017


FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	48" PPC I-BEAM STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -					CONTRACT NO.		
	PLOT DATE =	CHECKED -	REVISED -					ILLINOIS FED. AID PROJECT		




ELEVATION OF BEAM AT PIER




PLAN OF BEAM AT PIER



TOP PLATE




BOTTOM PLATE
(Showing threaded rods)




BOTTOM PLATE
(Showing studs)


See bearing details for pintle
hole locations when required.




LIFTING LOOP DETAIL




BAR G1(E)




BAR G2(E)



BAR G4(E)



G6(E) BAR ASSEMBLY



BAR G5(E)

BILL OF MATERIAL

Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete 1-Beams, 48"	Ft.	




NOTES

Inserts for 3/4" Ø threaded dowel rods, when specified, are to be two strut, ferrule type for interior beams and single ferrule, flared loop type for exterior beams. Prestressing steel shall be uncoated high strength, low relaxation 7-wire strand, Grade 270. The nominal diameter shall be 1/2" and the nominal cross-sectional area shall be 0.153 sq. in. The beams shall have a final concrete compressive strength, f'c, of psi and a release concrete compressive strength, f'ci, of psi. A minimum 2 1/2" Ø lifting pin shall be used to engage the lifting loops during handling. Tilt G6(E) bars when necessary to maintain 1 1/2" clearance. The top and bottom plates shall be AASHTO M270 Grade 50. The top and bottom plates shall be galvanized according to AASHTO M111. The threaded rods, nuts and washers shall be galvanized according to AASHTO M232. Threaded rods shall be ASTM F 1554 Grade 55. The G6(E) bar assembly shall develop, in tension, at least 125 percent of the yield strength of a grade 60 reinforcement bar times the nominal cross-sectional area of a #8 bar. The assembly shall allow completion of the splice without turning of the hook bar. The hook bar shall be threaded such that the entire coupler can be threaded onto the hook bar. Beams shall not be released from the fabricator until they have attained 45 days of age or older.

PI-4-48D

2-17-2017



FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	48" PPC I-BEAM DETAILS STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -					CONTRACT NO.		
	PLOT DATE =	CHECKED -	REVISED -					ILLINOIS FED. AID PROJECT		



BAR LIST
ONE BEAM ONLY
(For information only)

Bar	No.	Size	Length	Shape
G1(E)		#4	10'-7"	⏏
G2(E)		#4	8'-8"	⏏
G3(E)		#7		—
G4(E)		#3	4'-11"	⏏
G5(E)		#3	3'-5"	⏏
G6(E)		#8	6'-6"	⏏


Notes:
See sheet of for additional details
and Bill of Material.




PI-4-54

2-17-2017


FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	54" PPC I-BEAM STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -					CONTRACT NO.		
	PLOT DATE =	CHECKED -	REVISED -					ILLINOIS FED. AID PROJECT		




ELEVATION OF BEAM AT PIER




PLAN OF BEAM AT PIER




LIFTING LOOP DETAIL




BAR G1(E)




BAR G2(E)



BAR G4(E)




TOP PLATE




BOTTOM PLATE

(Showing threaded rods)




BOTTOM PLATE

(Showing studs)



G6(E) BAR ASSEMBLY



BAR G5(E)

BILL OF MATERIAL

Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete I-Beams, 54"	Ft.	

NOTES

Inserts for 3/4" ϕ threaded dowel rods, when specified, are to be two strut, ferrule type for interior beams and single ferrule, flared loop type for exterior beams. Prestressing steel shall be uncoated high strength, low relaxation 7-wire strand, Grade 270. The nominal diameter shall be 1/2" and the nominal cross-sectional area shall be 0.153 sq. in.

The beams shall have a final concrete compressive strength, f'_c , of psi and a release concrete compressive strength, f'_{ci} , of psi.

A minimum 2 1/2" ϕ lifting pin shall be used to engage the lifting loops during handling.

Tilt G6(E) bars when necessary to maintain 1 1/2" clearance.

The top and bottom plates shall be AASHTO M270 Grade 50.

The top and bottom plates shall be galvanized according to AASHTO M111. The threaded rods, nuts and washers shall be galvanized according to AASHTO M232.

Threaded rods shall be ASTM F 1554 Grade 55.

The G6(E) bar assembly shall develop, in tension, at least 125 percent of the yield strength of a grade 60 reinforcement bar times the nominal cross-sectional area of a #8 bar. The assembly shall allow completion of the splice without turning of the hook bar. The hook bar shall be threaded such that the entire coupler can be threaded onto the hook bar.

Beams shall not be released from the fabricator until they have attained 45 days of age or older.

PI-4-54D

2-17-2017

FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	54" PPC I-BEAM DETAILS STRUCTURE NO.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -							
	PLOT SCALE =	DRAWN -	REVISED -					CONTRACT NO.		
	PLOT DATE =	CHECKED -	REVISED -					ILLINOIS FED. AID PROJECT		